

RND/QT/XYZ/18-19
DATE: DD/MM/YYYY

QUOTATION

FEATURES OF THE POULTRY PROCESSING PLANT
(HYBRID PLANT 1500 GB 500 BPH)

SUITABLE FOR PROCESSING	BROILERS
WITH AN AVERAGE LIVE WEIGHTS OF	1.8 KG
MINIMUM WEIGHT	1.2 KG
MAXIMUM WEIGHT	2.5 KG
FOR AN HOURLY CAPACITY OF	500 BIRDS PER HOUR.
NUMBER OF SHIFTS	ON 1 SHIFT BASIS FOR 6 DAY A WEEK
BLEEDING TIME	240 SECONDS
FOLLOWING SCALDING SYSTEM	90 SECONDS AT 54 TO 56 DEGREES CELSIUS
PRODUCT	FRESH / CHILLED
EQUIPMENT LAID OUT FOR	220/440V, 3 PHASE, 50 CYCLES
POWER CONSUMPTION	APPROX. 12 TO 15 HP
WATER CONSUMPTION	8-10 LITRES PER BIRD

RND/QT/XYZ/18-19
DATE: DD/MM/YYYY

QUOTATION

HYBRID PLANT 1500 GB 500 BPH

SR.NO.	DISCRIPTION OF EQUIPMENTS	EX-FACTORY RATE INR
1.	<p>CRATE LOADING TABLE</p> <ul style="list-style-type: none"> ➤ Size 600mm X 600mm X 750 mm Height. ➤ SS 304 Constructed. ➤ Suitable to Load Live Birds Crate to hang on conveyer. 	8756
2.	<p>OVERHEAD CONVEYOR: 25 Mtr (Appx):</p> <ul style="list-style-type: none"> ➤ Round pipe track with trolleys 6 link, total 164 shackles & Trolleys. ➤ Stainless steel round pipe sections with stainless steel connector ➤ Clamps for fastening supports to steel construction ➤ Glass filled trolleys with Delrin wheels on stainless steel bearing Balls. ➤ Stainless steel Installation bolts/nuts ➤ 31 Mtr stainless steel connection chain ➤ 25 Mtr Galvanized calibrated hardened steel chain ➤ Shackle guiding rail hanging area ➤ 1 drive unit 180 Degree ➤ Drive with special Gearbox ➤ 1 tensioner set in a 180 Degree corner wheel ➤ 90 degrees/180 degree idler units ➤ 90 degrees up and down drive unit ➤ The Conveyor length <p style="text-align: right;">} as per final layout</p>	850000
3.	<p>STUNNING UNIT 0.8 mtr</p> <ul style="list-style-type: none"> ➤ Fiber glass water bath with electric stunning ➤ Complete with adjustable SS framework to suit various sizes of birds. ➤ Totally enclosed in Control Panel Box 	200340
4.	<p>KILLING TRAY (Small)</p> <ul style="list-style-type: none"> ➤ Stainless steel tray to kill birds by manual halal knife process ➤ Conical Hopper to collect blood in plastic tub. 	45896
5.	<p>BLEEDING TROUGH</p> <ul style="list-style-type: none"> ➤ Suitable for 4 minutes bleeding ➤ Stainless steel constructed trough to collect blood after halal. 	248778
6.	<p>HEAD PULLER</p> <ul style="list-style-type: none"> ➤ Automatic stainless steel constructed head puller ➤ Guide bars to position head prior to pulling. 	25324
7.	<p>SCALDING TANK</p> <ul style="list-style-type: none"> ➤ Total scalding length of 1.5 minutes made in SS 304, ➤ Temperature sensor ➤ Temperature probe with digital display. ➤ Air agitation system (Including Blower) ➤ Automatic heating by direct steam injection ➤ Over flow controller for controlling water level ➤ Stainless steel shackles guide rods and brackets 	740914

RND/QT/XYZ/18-19

QUOTATION

DATE: DD/MM/YYYY

	<ul style="list-style-type: none"> ➤ Range : -40 to 150 deg C, M34, LED display ➤ Output : 1 Prog DC PNP +4.20A analog, ➤ PT 1000 based TN2530 ➤ With 5 meter PUR wirable connector E10901 <p>(NOTE: BOILER NOT IN OUR SCOPE OF SUPPLY)</p>	
8.	<p>HOCK CUTTER</p> <ul style="list-style-type: none"> ➤ Stainless steel 90/180-degree model leg cutter ➤ 12/14" Stainless steel cutter fully adjustable 	310275
9.	<p>AUTOMATIC HOCK REMOVER</p> <ul style="list-style-type: none"> ➤ Stainless steel constructed guide rod & brackets ➤ After Hock Cutter to remove Hock from Shackle 	77824
10.	<p>AUTOMATIC CHAIN & SHACKLE WASHER:</p> <ul style="list-style-type: none"> ➤ Made of stainless steel and other Non-corrosive materials, ➤ Stainless steel frame ➤ Two vertical rotating nylon brushes, ➤ Driven by a electric motor & reduction gearbox ➤ Water spray nozzles 	272412
11.	<p>CENTRIPLUCK 1500 GB- SS 304</p> <ul style="list-style-type: none"> ➤ with door, gear box model ➤ Feather trolley + plastic crate – 1no. ➤ 1.5 hp 3 phase ➤ Approx. Load Capacity –22.5 kgs. 	161884
12.	<p>EVISCERATION TABLE 6'x4'x3' HEIGHT PERFORATED</p> <ul style="list-style-type: none"> ➤ With Pallet trolleys 2 Nos. ➤ Plastic crates 2 Nos. Drum: 1 No 	68068
13.	<p>ELECTRICALS & PANEL BOARD:</p> <ul style="list-style-type: none"> ➤ Stainless steel constructed ➤ Easy open able door ➤ Separate contactor & overload relay for each equipment ➤ Earth leakage circuit breaker ➤ Switch fuse unit for panel 	275706
14.	<p>DOUBLE SINK (5' x 2') WITH PLATFORM.</p> <ul style="list-style-type: none"> ➤ Stainless steel double sink for bird cleaning after evisceration ➤ Raised platform of around 1 Foot height. 	41265
15.	<p>SCREW CHILLER: 1.0 Dia. Wide X 3 mtr. Long</p> <ul style="list-style-type: none"> ➤ Made of stainless steel, ➤ Adjustable speed screw drive ➤ Fixed unloader, mounted at the screw shaft, ➤ Air blowers for proper agitation for washing the birds in portable water ➤ Chilling medium: chilled water/ flake ice ➤ Price excluding water chilling unit /flake ice unit. 	766301

RND/QT/XYZ/18-19
DATE: DD/MM/YYYY

QUOTATION

16.	<p>DRIP DRUM 2 mtrs</p> <ul style="list-style-type: none"> ➤ Excess water separator for wet birds. ➤ Made of stainless steel ➤ Rotating drum sieve with hydraulic variable speed drive 	406671
17.	<p>BIRD COLLECTION TABLE</p> <ul style="list-style-type: none"> ➤ 8' × 4' × 3' Stainless steel constructed table ➤ With height Adjustable leg for collecting the Birds 	55628
18.	<p>KLEEN KUT K1 0.5 (2 NOS)</p> <ul style="list-style-type: none"> ➤ ½ HP, Single Phase motor with 8" dia. ➤ SS hardened cutting blade. 	100682
19.	<p>KLEEN KUT TABLE WITH TRAY SS304 (2 NOS)</p> <ul style="list-style-type: none"> ➤ Completely in SS. 	65890
20.	<p>DEBONING CONES WITH TABLE</p> <ul style="list-style-type: none"> ➤ 6 × 4 × 3ft ht. stainless steel constructed table ➤ 4 deboning cone of Nylon with S.S.mounting pipe ➤ 6 Nos – 600mm × 400mm × 320mm plastic crates 	135599
21.	<p>S.S. PACKING TABLE:</p> <ul style="list-style-type: none"> ➤ 8 × 4 Stainless steel constructed table ➤ 2 Nos of bagging cone for packing the bird ➤ 6 Nos 600mm × 400mm × 220mm plastic crates ➤ 4 Nos 600 × 400 × 320 Plastic crates 	155649
TOTAL		5013862

AMOUNT IN WORDS: RS. FIFTY LAKHS THIRTEEN THOUSAND EIGHT HUNDRED AND SIXTY-TWO ONLY

PLEASE NOTE THAT THESE RATES ARE EX-WORKS:

RND/QT/XYZ/18-19
DATE: DD/MM/YYYY

QUOTATION

TERMS & CONDITIONS

GST: 18% APPLICABLE

LEVIES & OCTROI: AS APPLICABLE

PACKAGING, FORWARDING: EXTRA AT ACTUALS,

TRANSPORTATION & INSURANCE: EXTRA AT ACTUALS,

PRODUCT SPECIFICATION / S: ALL PRODUCT, PRODUCT SPECIFICATIONS AND DATA AS PER THE QUOTE ARE SUBJECT TO CHANGE WITHOUT NOTICE TO IMPROVE RELIABILITY, FUNCTION OR DESIGN OR OTHERWISE.

SUPERVISION FOR ERECTION & COMMISSIONING: AS TABULATED BELOW:

	<u>ADVANCE</u>	<u>TO CUSTOMERS ACCOUNT</u>				
	ALONG WITH ORDER FINALISATION	<u>VISA CHARGES</u>	<u>TRAVEL CHARGES</u>	<u>LOCAL TRANSPORT</u>	<u>LOCAL STAY</u>	<u>MEALS</u>
DOMESTIC	2,00,000 INR	NA	TRAIN- III AC	YES	YES	YES
ABROAD	REFER NOTE 1	YES	AIR TRAVEL	YES	YES	YES

NOTE 1: FOR FOREIGN INSTALLATIONS THE NET PAYABLE IS @ 100\$ PER PERSON PER DAY . THE SAME NEEDS TO BE WORKED ON PROBABLE DURATION AND WILL BE INVOICED WITH THE ORDER.

DELIVERY: 10 TO 12 WEEKS. FINAL DELIVERY PERIOD ON REQUEST.

PAYMENT TERMS: 100% ADVANCE ALONG WITH PURCHASE ORDER.

GUARANTEE: ONE-YEAR GUARANTEE AGAINST ANY MANUFACTURING DEFECTS. THIS DOESNOT COVER RUBBER FINGERS, BEARINGS & CHAIN THAT WEAR OUT WITH USAGE OR ANY OTHER WEAR PARTS.

NOT IN OUR SCOPE OF SUPPLY: - ALL ELECTRICAL CONNECTIONS, WATER & SEWAGE CONNECTION TO THE POSITION OF THE MACHINES TO BE CARRIED OUT BY YOU. WELDING MACHINE, GENERAL TOOLS AND CASUAL LABOUR AND CIVIL WORK INCLUDING MS CHANNELS OF ANY KIND REQUIRED FOR ERECTION AND COMMISSIONING TO BE SUPPLIED BY YOU.

RND/QT/XYZ/18-19
DATE: DD/MM/YYYY

QUOTATION

STATUTORY AND REGULATORY REQUIREMENTS:

- 1) Without final layout sanction from customer and RND Automation Pvt. Ltd. Internal work order will not be processed. And this processing time will be not included in final commitment of delivery.
- 2) Water – Proper water supply for Dressing and cleaning
- 3) Electrical supply phase is required as per machinery.
- 4) LPG- No Objection Certificate – Commercial gas connection should be there.
- 5) Sufficient space and building is required as per machinery layout.
- 6) Pollution control board certificate is required if necessary.
- 7) Shop Act license/ Factory act license required if necessary.
- 8) HACCP certificate is required if necessary.

SUPERVISION OF INSTALLATION AND COMMISSIONING

- 1) Comprehensive charges of Installation and commissioning as per pro-forma invoice
- 2) The installation will be effected according to a final layout to be approved by the client.
- 3) All installation and commissioning work should be completed within 6 months after B/L date.
- 4) Prior to and during installation and commissioning, you should see to:
 - a. Installation of all equipment that is not part of scope of supply
 - b. Transportation from site to hotel and back.
 - c. Sufficient testing material, as required by our engineer
 - d. All tools, as well as hoisting and lifting equipment required for installation
 - e. Sufficient skilled staff comprising of an electrician, welder, plumber, two mechanics and sufficient unskilled workers.

NOTE: -

- A) PRICES VALID FOR 60 DAYS FROM DATE OF QUOTATION.
- B) ADVANCE RECEIVED IS NOT REFUNDABLE.
- C) ONCE EQUIPMENT IS READY IT HAS TO BE COLLECTED WITHIN 30 DAYS OF INTIMATION OTHERWISE INTEREST WILL BE CHARGED AT 24% ON THE BALANCE AMOUNT.
- D) IN THE EVENT THAT WE HAVE TO PACK AND FORWARD THE EQUIPMENT, EXPLICITE INTSTRUCTIONS SHOULD BE GIVEN BY THE BUYER AND IT WILL BE DONE TO HIS COST.

THANKING YOU,
YOURS SINCERELY

FOR RND AUTOMATION PVT. LTD.

AUTHORISED SIGNATORY